KADUR FOREST DIVISION.

Abstract Notification dated 6th September 1937.

The attention of the public is invited to the detailed notification, calling for tenders for carting timber to the several depots, during 1937-38, published on pages 1515-1516, Part VI of the *Mysore Gazette*, dated 16th September 1937.

M. A. MUTHANNA,
District Forest Officer.

CHITALDRUG DISTRICT.

Abstract Notification dated 9th September 1937.

The attention of the public is hereby invited to the detailed notification of date, published on pages 1516-1518 of Part VI of the *Mysore Gazette*, dated 16th September 1937, calling for tenders for clearing and fire tracing the demarcation lines of Several Forests of the District.

Further particulars may be ascertained from the office of the undersigned.

Abstract Notification dated 16th September 1937.

The attention of the public is invited to the detailed Notification, calling for tenders for the supply of rations to the Departmental Elephant working at Hiriyur, during the current year, etc., published on pages 1567-1568 of the *Mysore Gazette*, Part VI, dated 23rd September 1937.

A. V. KESAVIENGAR,
District Forest Officer.

ENGINEERING DEPARTMENT

BUREAU OF SANITARY ENGINEERING, BANGALORE.

Notification dated 20th September 1937.

Notice is hereby given that sealed tenders will be received at the Office of the Sanitary Engineer, Bureau of Sanitary Engineering, Bangalore, up to 1 P.M. on 11th October 1937, for extending the existing office building of the Superintendent, Vani Vilas Water Works, Mysore. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of March 1938.

2. The plans, detailed estimate and conditions may be seen at the Sanitary Engineer's Office between the hours of 11 A.M. and 5 P.M. on all office days.

3. Tenders should be submitted on printed forms which may be obtained from the Sanitary Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of Rs. 455 in cash (no cheques will be accepted) as earnest money, and be superscribed "Tender for Extending the existing office building of the Superintendent, Vani Vilas Water Works, Mysore," in default of which the tenders will be rejected.

5. The final acceptance of the tender will rest with the Sanitary Engineer who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond, in default of which his tender will be considered cancelled and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the Notice Board in the Sanitary Engineer's Office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

9. Charges on account of scaffolding materials, implements for setting out, barricading, clearing site, supply of water, etc., that may be found necessary during execution will not be paid for separately but should be borne by the contractor.

10. Rates for non-tendered and non-estimated items shall be as per schedule rates of the Department or those fixed by the Sanitary Engineer after working out data with not more than 10 per cent for contractor's profit.

11. In all matters not specifically provided for and in all matters of disputes about rates, quantities, measurements, quality of works, etc., and in all disputes of any kind, the decision of the Sanitary Engineer will be final and legally binding.

Estimate of the Approximate quantities for extending the existing Office Building of the Superintendent, Vani Vilas Water Works, Mysore.

No.	Particulars	Unit	Quantity.
1	Earthwork excavation in hard gravelly soil and filling in basement with watering and consolidation	C.yd.	1,062
2	Stone jelly concrete in lime mortar	C.ft.	1,028
3	Burnt brick in lime mortar	"	3,273
4	Burnt brick in mud	"	2,883
5	Burnt stone slabs dressed and fixed 6″ thick two lines dressed	S.ft.	969
6	Supplying and fixing new teakwood doors with panelled shutters, hinges, frame bolts, etc., complete	"	324
7	Supplying and fixing new teakwood windows with glazed shutters inside and iron bars including frame, hinges, hooks, etc., complete	"	396
8	Supplying and fixing new teakwood windows with pannelled shutters including frame, hinges, bolts, etc., complete for store room at rear	"	30
9	Supplying and fixing new teakwood ventilators glazed	"	16
10	Supplying and fixing large door for store room at rear	"	100
11	Supplying and fixing burnt stone pillars 8″×8″ square 2 lines dressed with pedestal and capital, etc., complete and 8 feet high each	No.	26
12	Supplying and fixing Rolled steel joists for verandahs, etc.	Cwt.	31·5
13	Teakwood wrought and put up including 2 coats of wood oiling	C.ft.	217·16
14	Teakwood wall plates 2½″×3½″ treated with 2 coats of tar including fixing	R.ft.	422
15	Flat diagonal terrace with two courses of tiles laid edgewise and two courses of flat tiles laid thereon, Kappi, etc., including plastering top and bottom surfaces with lime mortar and whitewashing ceiling two coats, complete	Sqr.	12·73
16	Roofing with first class Mangalore tiles over teak reepers including two coats of wood oiling to reepers, etc., complete	"	23·64
17	Ridge tiles set in lime mortar and jointed with cement	R.ft.	149
18	Constructing mortar bands over roofing of store room at rear	"	40
19	Plastering with lime mortar ½″ thick	Sqr.	76·02
20	Colour washing two coats	"	34·87
21	Whitewashing two coats	"	39·62
22	Constructing parapet with burnt brick in lime mortar, plastering cornices and coping, whitewashing, etc., complete	R.ft.	201
23	Flooring with 3″ lime concrete plastered over with red ochre mixed with cement mortar ½″ thick, and cut to squares to resemble square tiled flooring	Sqr.	23·88
24	Ornamental cornice in burnt brick in lime mortar 12″ deep including plastering, whitewashing, etc.	R.ft.	196
25	String cornice in burnt brick in lime mortar 8″ deep including plastering, etc., complete	R.ft.	293
26	Boxing rolled steel joists with burnt brick in cement mortar, wire netting, plastering, etc., complete	"	210
27	Painting with dark grey paint, two coats	Sqr.	23·54
28	Supplying and fixing rain water zinc spouts from terrace	No.	20
29	Removing existing windows and converting the openings to doorways	S.ft.	36
30	Removing the existing windows and converting the openings to wall shelves	S.ft.	36
31	Making opening in existing wall for door-way including building up sides in burnt brick in lime mortar, plastering, etc., complete	S.ft.	15

N. KRISHNIENGAR,
Sanitary Engineer.

BANGALORE DIVISION.

Notification dated 2nd September 1937.

It is hereby notified for the information of the public that unserviceable stores will be sold by public auction on the 25th October 1937 at 8 A.M., in the premises of the Office of the Executive Engineer, Bangalore Division, Bangalore. The terms and conditions of the sale are:—

(*a*) The articles will be sold in lots and knocked down to the highest bidder. In the event of any dispute arising between two or more bidders offering the same price, the lot or lots shall be put up again and resold.

(*b*) All articles purchased shall be at the risk of the purchaser thereof from the time of sale.

(*c*) Cash shall be paid in full for lots purchased by bidders before delivery and the articles shall not be permitted to be removed from the place of auction until the sale is confirmed by the Executive Engineer.

(*d*) In case of default of payment of purchase money by any bidder, the articles shall be resold at the risk and cost of the bidder who shall also be liable to make good the Government losses arising thereby.

(*e*) The following is the list of articles available for sale :—

Survey and Mathematical Instruments.—

	No.
Metallic Tape 50'	3
Refills 50'	3
Famine Reserve Tools.—	
Stone Breaking Hammers	6
Tools and Plant.—	
Axis, Pick	5
Buckets, Galvanized	6
Iron Pots	14
Locks, Common	2
Mumties	28
Pans, Mortar	12
Trap, Rat	1
Tent Iron Pegs	12
Flat Iron Rafters	5
Empty Steel Barrels	2
Iron Hooks, Round	23
Hand Brass Lanterns	2
Spare parts of S. R. R.	7
Cast Iron Pipe 4" tail piece, 1' 5" long	1
Lantern Dietz	3
Pump Shaft M. S.	1
M. S. Rod 2'	1

D. A. HUKERI,
Executive Engineer.

MYSORE DIVISION.

Abstract Notification dated 14th September 1937.

The attention of the public is hereby invited to the Advertisement, published on pages 1569-1571 of the *Mysore Gazette*, dated 23rd September 1937, Part VI, calling for tenders for the work of constructing a Local Fund Dispensary at Periapatna, Hunsur Taluk.

The last date of receipt of tender is 9th October 1937.

B. KRISHNA RAO,
Executive Engineer.

SHIMOGA DIVISION.

Notification dated 23rd September 1937.

Notice is hereby given that sealed tenders will be received at the Office of the Executive Engineer, Shimoga Division, up to Monday, the 25th October 1937, for Restoring Chettanhalli Hirekere Reg. No. 38 of Honnali Taluk, and filling up the breach and lowering the draft channel of the weir. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of June 1938.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's Office at Shimoga Division, between the hours of 11 A.M. and 5 P.M.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of Rupees one hundred and ninety-five only in cash or Government Promissory Notes as earnest money, and be superscribed "Tender for Restoring Chettanhalli Hirekere Reg. No. 38 of Honnali Taluk, and filling up the breach and lowering the draft channel of the weir," in default of which tenders will be rejected.

5. The final acceptance of any tender will rest with the Executive Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond, in default of which his tender will be considered cancelled and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the Notice Board in the Executive Engineer's Office in due course. No enquiry regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

9. Rates once tendered will not be enhanced on any account.

10. Rates for non-tendered and non-estimated items shall be as per schedule rates of the department or those fixed by the Executive Engineer after working out data with not more than 10 per cent for contractor's profit.

11. In all matters not specifically provided for and in all matters of dispute about rates, quantities, measurements, quality of works, etc., and in all disputes of any kind, the decision of the Executive Engineer will be final and legally binding.

12. Quotations must be given in words as well as in figures and they must be in specific term of unit shown against each item of work. Any quotation quoted at so much percentage less or more than estimated rate will not be accepted.

Abstract estimate for Restoring Chettanhalli Hirekere Register No. 38 of Honnali Taluk and filling up the breach and lowering the draft channel of the weir:

No.	Items of work	Unit	Rate	Quantity
			Rs. a. p.	
1	Earthwork excavation, foundation for breach filling ..	C.yd.	0 4 0	1,427
2	Breach-filling mixed with 30 per cent selected earth including watering and consolidation including lead.	,,	0 4 0	1,427
3	Breach filling with excavated earth from lead off channel from 33·00 to 55·00 with 30 per cent gravel including lead	,,	0 7 0	1,552
4	Putting puddle core wall with selected clay mixed with 25 per cent gravel	,,	0 12 0	385
5	New stone revetment including jelly backing 6" thick ..	,,	2 0 0	632
6	Turfing in front and rear slopes	Sqr.	0 10 0	80·40
7	Excavating a lead of channel in the tank bed near the breach to the weir bed width 18' and side slopes 1½:1 and using the same for bund dry filling and forming at low places	C.yd.	0 4 0	1,663
8	Excavating draft channel of weir in hard and stoney soil	,,	0 5 0	877
9	Draft and approach clearing at waste weir for extra 6' length of weir	L. S.	..	..

P. SUBBA RAO,
Executive Engineer.